

Dew Point Control Unit

Client ENI Australia

Project Blacktip Development Project

Location Northern Territory, Australia

Delivery 2009

Plant Details

Gas Throughput: 135 MMSCFD

Inlet Temperature: 33 °C

Inlet Pressure: 5,860 kPag

Outlet Specification: -10 °C @ 5,900 kPag



Image of ENI Blacktip Dew Point Control Unit during delivery,
Northern Territory 2009