

# TEG Dehydration

Client Occidental Oman

Project Jalal Production Facility

Location Oman

Delivery 2012

## Plant Details

Gas Throughput:	30 MMSCFD
Lean TEG Circulation Rate:	3.6 USGPM
Outlet Water Content:	< 1.75 lb / MMSCF
Outlet Dewpoint:	-29 °C

