

Gas Dehydration - TEG

Client HESS

Project Jambi Merang Gas
Production Facility

Location Indonesia

Delivery 2010

Plant Details

Gas Throughput: 80 MMSCFD

Lean TEG Circ. Rate: 9.5 USGPM

Lean TEG Conc.: 99.6 wt%

Outlet Water Content: < 10 lb / MMSCF



TEG Dehydration package being delivered from
Batam works', Indonesia 2010