

Gas Dehydration - TEG

Client AGJV / ONGC
Project ICP-R Process Platform Project
Location Offshore, India
Delivery 2010



ICP-R TEG regeneration skid ready for delivery from Process Group International's works, Abu Dhabi 2010

Plant Details

Gas Flowrate: 90 MMSCFD
Lean TEG Circulation Rate: 18 USGPM
Lean TEG Concentration: 99.7 wt%
Outlet Water Content: < 5 lb / MMSCF