

Gas Dehydration - TEG

Client Oil Search

Project PNG LNG Associated Gas & Related Projects

Location Papua New Guinea

Delivery 2011

Plant Details

Gas Throughput: 3 x 100 MMSCFD

Lean TEG Rate: 46 USGPM

Lean TEG Purity: 99.89 wt%

Outlet Water Content: 5 lb / MMSCF

Stripping Gas Rate: 0.15 MMSCFD



Installed TEG Dehydration package, Papua New Guinea.