

# Gas Dehydration - TEG

Client Santos

Project Fairview CS3 Project

Location Queensland,  
Australia

Delivery 2008

## Plant Details

Gas Throughput: 2 x 30 MMSCFD

Lean TEG Rate: 7.1 USGPM

Operating Pressure: 11,200 kPag

Gas Dewpoint Spec.: < 4 lb / MMSCF

Lean TEG Purity: 99.6 wt%



TEG skids being installed onsite, Fairview 2008.