

Gas Dehydration - TEG

Client Fluor / Santos

Project GLNG Upstream Project

Location Queensland

Delivery 2012

Plant Details

Gas Flowrate:

Roma - 2 x 85 MMSCFD

Fairview - 5 x 100 MMSCFD

Lean TEG Circulation Rate: 17.5 USGPM

Lean TEG Concentration: 99.65 wt%

Outlet Water Content: 4 lb / MMSCF



Two TEG Dehydration packages nearing completion at Process Group's works, Rowville 2012