

Gas Dehydration - TEG

Client Origin Energy

Project Talinga Gas Plant

Location Queensland, Australia

Delivery 2009

Plant Details

Gas Throughput: 3 x 60 MMSCFD

Lean TEG Rate: 12.63 USGPM

Lean TEG Concentration: 99.56 wt%

Stripping Gas Rate: 26 SCFM



TEG Regeneration skids nearing completion at Process Group's works, Rowville 2009.