

Amine CO₂ Removal

Client BHP Petroleum

Project Zamzama Phase II Project

Location Pakistan

Delivery 2007

Plant Details

Untreated Gas Flowrate: 161 MMSCFD

Untreated Gas CO₂ Content: 3.49% vol/vol

Treated Gas CO₂ Content: 0.01% vol/vol

Lean Amine Flowrate: 720 USGPM



Amine contactor (left) and regenerator installed onsite, Pakistan 2007.